





























MASTER PARCEL LOCKER (REQUIRED) 20-DOOR (1065MM)

IP cameras & NVR + Pin hole comes with Master Unit - will be mounted to survey overall installation

Operating on an ISO27001 Certified IT Infrastructure

Fire rated for Canada to CAN/ULC-S102

Electrically Certified for Canada to CSA C22.2 No.62368-1:19

Wall Clearance

100mm back wall clearance to vent CPU 25mm side wall clearance 25mm ceiling clearance 25mm ceiling clearance from top of cameras (if cameras are installed)

Electrical

Standard 15amp grounded plug 48" AFF (centered behind master unit) -100w draw

Ethernet

Cat5/6 48" AFF(centered behind master unit) OR Wi-Fi

The expansions connect to the master via 24v low voltage and ethernet connections - installed by Snaile



Scan QR Code to find out!



CONFIDENTIAL

